

ULUBERIA MUNICIPALITY

ULUBERIA + HOWRAH

RENOVATION OF ULUBERIA RABINDRA BHAVAN.

The rates are based on P.W.D. Schedule of rates (Building Works) Volm- 1 w.e.f. 1st July, 2014.

Sl. No.	Description of Items	Quantity	Unit	Rates	Amount
[1]	[2]	[3]	[4]	[5]	[6]
1	Supplying , fitting and fixing boiling water resistant ply.....as per design as per approval and direction of Engineer-in-Charge. In Ground Floor 9 mm. [Vide Page No. 122, Item N o. 108(iii)]	173	SQ.M	1192.00	206216.00
2	Partition of teak veneer (1mm) as per design fitted and fixed complete. In ground floor 4 mm. thick commercial quality. [Vide Page No. 127, Item N o. 124(i).]	173	SQ.M	537.00	92901.00
3	(A) Wood work in posts, post plates, rafters, battens, truss members, purlins etc. but including the cost of nails, screws etc. Sal local [Vide Page No. 86, Item N o. 3(A)(ii)]	0.105	CU.M	89345.00	9381.22
4	Supplying best Indian sheet glass panes set in putty Nails complete. 4 mm. thick [Vide Page No. 166, Item N o. 2(ii)]	9.775	SQ.M	972.00	9501.30
5	(a) Rendering the surface of walls and ceiling with plaster of paris (thickness not less than 1.5mm.). [Vide Page No. 161, Item Sl. N o. 5(a)]	46.20	SQ.M	64.00	2956.80
6	Applying interior grade acrylic primer of approved quality and brand on plastered or concrete surface direction of EIC. (b) Two coats. (i) Water based interior grade acrylic primer. [Vide Page No. 157, Item Sl. N o. 14(b)(i)]	61.00	%SQ.M	4798.00	2926.78
7	Applying Acrylic Emulsion Paint of approved make and brand on walls and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Superintending Engineer). [Vide Page No. 163, Item Sl. N o. 9(i)]	61.00	SQ.M	67.00	4087.00
8	Asbestos corrugated (Trafford or similar approved quality) sheet (6mm. thick)..... side lap complete. In Roof [Vide Page No.- 62, Item No.- 23(a)]	54.00	SQ.M	549.00	29646.00

9	Supplying, fitting and fixing 10 litre P.V.C. low-down cistern conforming to I.S. Specification with P.V.C. fittings complete, C.I. brackets including tow coats of painting to bracket etc. [Vide Page No.27, Item Sl. N o. 2]	2.00	Each	1181.00	2362.00
10	Providing and fixing of false ceiling with powder coated exposed G.I.grid suspension system..... of approved pattern and size. (a) Acoustic false ceiling (with 15mm. thick OW Acoustic Board and E-grid U-1520). [Vide Page No. 119, Item Sl. N o. 100(a)]	9.00	SQ.M	1371.00	12339.00
11	French polishing to wood work including preparing surface (ordinary gloss) On old French polished surface including complete removal of the old polish. [Vide Page No. 164, Item Sl. N o. 18(b)]	200.00	SQ.M	563.00	112600.00
12	Supplying fitting and fixing granite slabs 15mm. to 18mm. thick with uniform texture.....curing and roughening of concrete surface complete. [Vide Page No. 55, Item Sl. N o. 31(B)]	25.38	SQ.M	2680.00	68018.40
13	Sound system at Rabindra Bhavan with Amplifier (AHUZA) sound box, microphone with stage Mike (Catcher) and wire.			L.S.	247000.00
				Total Rs.	799935.50
				Say Rs.	799936.00

Sub-Assistant Engineer,
Uluberia Municipality

Assistant Engineer,
Uluberia Municipality

Executive Officer,
Uluberia Municipality